

APPLICATION

Type UA & UC trims are used to create an upstand detail in mineral fibre, g.r.g, plasterboard or full module metal suspended ceiling tile systems where a vertical plasterboard or m.d.f upstand is required.

PRODUCT INFORMATION

Supplied in 3000mm lengths, extruded from architectural grade aluminium alloy to BS 1474. The standard finishes are white polyester powder coating to RAL 9010, 20% Gloss, or to order in a full palette of RAL colours, to match and enhance any interior scheme. Unpainted trims also available for onsite painting/spraying, please check with your paint supplier for any additional primer products that may be required. QIC cannot accept any responsibility for the painted finish of products supplied unpainted. Non-standard lengths, factory curving and alternative factory applied finishes are available to special order. Wedgelock cleats to form straight joints, internal and external corners and abutment details are also available to order separately



PACKING

Packed in quantities as ordered with no bundle exceeding 25kgs. Packaging is by heavy gauge heat shrink polythene with corrugated cardboard end protection.

TECHNICAL DETAILS

Designed specifically for use with suspended ceiling systems where the infill tiles are metal, mineral fibre, g.r.g, plasterboard or rigidised mineral wool. All trims have the structural capacity to support the type of infill tiles they are designed to be used with, and a substantial factor of safety has been allowed for in their design. However, trims are not designed to support loads other than their infill loads and due consideration should be given to independent support for any additional imposed loads from items such as light fittings, air conditioning units etc. Perimeter trims can have a bead of silicone mastic applied between the trim and the wall to improve both the aesthetic appearance and sound insulation if required. Perimeter trims should always be backed with a layer of wall boarding material and should never be fixed directly in contact with the building structural framing.

UA01



UC01

